

Executive Summary

Greater Manchester's leaders have proposed a **London-style underground metro** to relieve surface congestion, boost capacity and support the region's economic growth [3†L69-L76] [80†L74-L82] . This report evaluates strategic objectives, three candidate network options, engineering and operational requirements, costs and funding models, governance and delivery, plus socioeconomic and environmental impacts. We compare options (in tables) and illustrate routes (maps/schematics) and timelines. Key findings include:

- **Strategic Goals:** The underground would **integrate with the Bee Network**, extend capacity for growth and jobs, and advance net-zero transport. A unified, high-capacity metro aligns with GM's transport strategy of a *"new underground system for trains and trams"* to increase capacity [31†L3774-L3782] . It also targets 75,000 new homes and £90 bn uplift around major rail hubs by 2050 [80†L101-L104] .
- **Network Options:** We develop **three route concepts**:
 - *Option A:* A Metro-style loop tapping dense suburbs (e.g. Altrincham–City–Bury) via deep tunnel beneath the core tram lines [55†L75-L83] .
 - *Option B:* A cross-city heavy-rail tunnel (eg. Preston–Manchester–Stockport) linking mainline corridors and easing the Castlefield bottleneck [55†L89-L93] [80†L92-L94] .
 - *Option C:* A new airport spur (Northern Gateway–Manchester Airport) reaching under-served southern/north-west areas [55†L89-L93] .Each option's stations and interchanges with existing Metrolink, heavy rail and buses are detailed, with phased construction sequences. Tables compare length, stations, cost and benefits of each.
- **Engineering:** Tunnels would use TBMs in mixed geology (Quaternary clays, sandstones). Stations mix shallow cut-and-cover (city centre stops) and deep-bore caverns. New shafts (ventilation/escape) and a depot outside the core (e.g. at Trafford or Airport) are needed. Extensive utility diversions and ground surveys are required. Geotechnical risks include soft clays and water inflows in Manchester's basin [80†L82-L90] . Modern station design (long platforms, full accessibility) is assumed.
- **Capacity & Operations:** Each line could run 24–30 trains/hr, carrying ~15–20k passengers/hour/direction (PPHPD) at peak (comparable to London Underground levels). Trains likely EMUs of 4–8 cars (similar to London Overground/Elizabeth line) with regenerative power. Automatic signalling (CBTC) would enable high frequency. Lines would be run by a "Manchester Metro" concession under TfGM/TfL-style management, integrated fare-wise into the Bee Network (contactless tickets). Rolling-stock procurement could follow TfL models (e.g. Bombardier/Hitachi trains).
- **Costs & OPEX:** Capital costs are of order **£0.3–0.5 bn per km**. For example, 3.5 km Northern Line ext cost £1.1 bn [50†L10733-L10734] (~£314M/km), while Crossrail's 42 km central tunnels cost ~£18.9 bn [43†L270-L274] [44†L13-L21] (~£450M/km). We estimate each GM metro option at £5–12 bn total (including stations and systems). Operating costs might run £20–30M per km per year (~£300–600M/year network-wide), roughly 3–5% of capex. A sensitivity range (±30%) is shown in tables.
- **Financing & Revenue:** A mix of funding is required: central grants (Department for Transport/City Region Sustainable Settlement), local borrowing (GMCA/TfGM bonds), and private

contributions. Options include **PPP** or DB contracts for construction, and franchise or concession for operations. Innovative sources – such as a local business levy/CIL (as used for Crossrail [61†L1092-L1100]), station over-site development, and Metro Mayoral bonds – could raise capital. Public funding is likely necessary given scale. Revenue would come mainly from fares (integrated with Bee pricing) – perhaps covering a fraction of OPEX – with the rest subsidised. We consider scenarios: e.g. a modest congestion charge or workplace levy could add funds (though politically challenging). Tables outline funding mixes and farebox projections.

- **Governance & Delivery:** The GM Combined Authority (Mayor/TfGM) would champion the scheme, with oversight from a new Metro Delivery Board. Procurement would likely follow DfT/PIUs: separate contracts for TBMs, civils, systems, and rolling stock (possibly with PPP elements). A Transport and Works Act Order or Planning Act consent would be needed (with full EIA). We propose a phased programme from 2026 (feasibility) through 2050 (final opens), as shown in the Gantt chart below. Key risks include cost overruns, planning delays, geotechnical surprises, and financing shortfalls; a risk register itemises mitigation strategies.
- **Economic & Social Impact:** A new metro would create **thousands of construction jobs** and stimulate local economies. For example, Crossrail's build phase supported ~55,000 UK jobs [72†L76-L79] . By vastly improving connectivity, the underground could generate billions in GVA: Greater Manchester's strategy predicts ~£90bn uplift by 2050 around transformed hubs [80†L101-L104] . Property values and development prospects would likely rise near new stations. Substantial **modal shift** from cars is expected: transport is ~1/3 of GM's CO₂ emissions [76†L1532-L1536] , so higher transit usage would cut pollution. We model scenarios: even a 10–20% reduction in car trips (via 200–400m extra metro journeys/year) could save ~0.1–0.2 MtCO₂ annually. Social benefits include better access to jobs and services in peripheral areas, improving inclusion. More detailed cost–benefit estimates are tabulated for each option.
- **Environment & Planning:** All routes would require full environmental impact assessments. The tunnel scheme has lower surface footprint than at-grade lines, but stations and shafts have local impacts. Early works must manage archaeology (Manchester has rich heritage) and minimise disruption. Compared to at-grade rail, the underground would reduce noise and visual intrusion in the long term. We identify required consents (Planning Act Orders, railway works orders, listed-building consents, etc.) and outline timelines for statutory processes.
- **Stakeholder Engagement:** Robust consultation is essential. Previous GM schemes (Bee Network, HS2) show strong local interest in transit. Mayoral press releases and council statements (e.g. Bury leader applauding “thinking outside the box” [55†L99-L103]) suggest political support. A comprehensive plan would involve workshops with local authorities, businesses (e.g. Mayfield Partnership, airport), and residents along routes. Web consultations and exhibitions (as in GM's 2050 transport strategy process) should be staged, feeding into design choices. An ongoing communications campaign would emphasise benefits (jobs, regeneration, cleaner air).

This report provides detailed analyses under each heading, with comparisons in tables and illustrative diagrams. The **Mermaid timeline** and cost breakdown chart below summarise key data. References to UK official sources, TfGM documents and case studies are cited throughout.

Strategic Objectives

Greater Manchester's transport strategy sets out a vision of a **fully integrated Bee Network** of bus, tram and rail. The metro proposal directly supports this by linking existing networks in a single system [3†L69-L76] [17†L513-L520] . Key objectives include:

- **Capacity & Connectivity:** GM's city centre corridors (e.g. Castlefield rail, busiest Metrolink lines) are already overburdened [80†L92-L94] [55†L75-L83] . An underground network would

“increase [tram/rail] capacity” in the core 【31†L3774-L3782】 without requiring new surface land. It also provides faster cross-city journeys, easing pressure on radial routes. The region aims to double rail trips by 2040 【80†L88-L90】 and to connect major hubs (airport, Piccadilly, University, etc) more directly.

- **Economic Growth & Housing:** Transport investment is seen as a catalyst for jobs and development. The GM rail strategy explicitly links the underground to **regeneration**: e.g. a new Piccadilly “superstation” could unlock 75,000 homes and ~£90 bn economic uplift 【80†L101-L104】. Similarly, other interchange hubs would become focus points for office and residential schemes, mirroring cross-London examples. The metro would support the Northern Powerhouse agenda by improving airport and intercity rail access, boosting the North’s productivity 【38†L101-L104】 【80†L101-L104】.
- **Social Inclusion:** A truly regional metro could extend into underserved districts, improving job access and inclusion. GM leaders emphasise *“levelling up”* and widening opportunities through transport 【3†L69-L76】. Off-peak service all day would benefit shift workers and disabled passengers more than infrequent regional rail. Integration with affordable Bee fares ensures fairness across income groups.
- **Environment & Decarbonisation:** Transport is ~⅓ of GM’s CO₂ emissions 【76†L1532-L1536】. By attracting people from cars to clean electric rail, the metro would cut emissions and congestion. This aligns with the region’s net-zero target (2038) and air-quality plans. Also, putting Metrolink and trains underground reduces street-level impacts (noise, visual blight) and frees space for pedestrian/public realm improvements. Combined with EV buses and cycling, the project fits GM’s “zero-emission” transport goals 【76†L1546-L1554】.

These strategic goals are echoed by officials. The GM Mayor and TfGM have repeatedly described a *“London-style integrated network”*, citing improved accessibility, cleaner air and economic success 【3†L69-L76】 【80†L74-L82】. The 2050 Transport Strategy explicitly calls for *“tunnelled metro options”* in the regional centre 【31†L3774-L3782】. In sum, an underground metro is seen as a long-term enabler for GM’s growth, sustainability and social targets.

Network Options

We consider **three options**, each forming a distinct line or link. All routes are conceptual but reflect known demand corridors 【55†L75-L83】 【80†L92-L94】. Stations are located at major centres and interchanges with Metrolink, mainline rail and bus, to ensure full integration.

Option A: Altrincham–Bury Metro Tunnel

- **Route:** Follows the busy *Altrincham – Piccadilly – Bury* corridor (tracing Metrolink’s Green and Red lines). Northbound from Altrincham through Old Trafford, Deansgate, St Peter’s Square, Victoria and onward to Bury.
- **Key Stations:** Altrincham, Old Trafford, MediaCity (tram link), Deansgate-Castlefield, St Peter’s (Oxford Road), Manchester Victoria, Salford Crescent, Victoria, Bury Interchange.
- **Interchanges:** At Victoria and Piccadilly with mainline rail; at Oxford Road with Metrolink; bus interchanges at major stops. Potential new “Cross-Platform” interchange created between Metrolink and the underground at key city stations.
- **Phasing:** Phase 1 could be central Manchester (Altrincham–Victoria), where demand is highest and land costs steep; Phase 2 extends north to Bury.

- **Benefits:** Relieves the two busiest Metrolink lines (bypassing congestion on Bridgewater/Victoria interchanges) 【55†L75-L83】 . Provides high-capacity service along a densely populated spine. Initial section (Altrincham–Victoria) covers several critical hubs.

Option B: Cross-City Heavy-Rail Tunnel

- **Route:** Links existing heavy-rail axes *Blackpool/Preston* lines in the west through a tunnel beneath Manchester city centre to *Manchester Airport/Stockport* lines in the south-east. Roughly parallels the Castlefield Corridor but on a new alignment.
- **Key Stations:** Trafford Park (for industry and tram interchange), Deansgate, Manchester Piccadilly (new deep through-station under the existing one), Ardwick, Heaton Park, and Airport (forming a loop to the south).
- **Interchanges:** Direct connection at Piccadilly with Northern Powerhouse Rail; at Deansgate with Salford Crescent (Metrolink), and at new Airport hub (Metrolink and national rail).
- **Phasing:** Could begin with western leg (Trafford–Piccadilly) linking into Northwest Rail Resilience, then extend eastwards through Ardwick to Airport.
- **Benefits:** Frees the overloaded Castlefield rail corridor (Northern/Northwest & TransPennine services) by shifting local trains underground 【80†L92-L94】 . Creates a fast cross-city link between western and southern suburbs. Integrates NPR (HS2) with Manchester’s local network seamlessly.

Option C: Northern Gateway – Airport Line

- **Route:** A new southern loop from the “Northern Gateway” (Salford/Trafford area of planned urban expansion) south-east under the city to Manchester Airport. Essentially a second, more direct Airport connection supplementing the longer routes via Stockport.
- **Key Stations:** Pomona (MediaCity), Port Salford/Northern Gateway (future development), a city-centre stop (e.g. Piccadilly East), Manchester Airport.
- **Interchanges:** Connects with Metrolink at Pomona; with Piccadilly via a short tunnel; with other Option B line at Airport. Provides a second Metro link to airport, improving resilience.
- **Phasing:** Could be built as one package or linked to Option B. Alternatively, start at Airport–Pomona and add city spur later.
- **Benefits:** Opens up large Brownfield “Northern Gateway” for housing/employment. Provides a faster shuttle between airport and city centre without following existing rail path via Stockport. Bypasses congested southern rail approaches.

Comparison of Options

Option	Route description	Length (est.)	Major Stations	Key interchanges	Notes/Pros
A. Altrincham–Bury Metro	Under central Manchester along Metrolink corridor 【55†L75-L83】	~18 km	Altrincham, Deansgate-Castlefield, Oxford Rd, Victoria, Bury	Victoria/Piccadilly (rail), Deansgate/Victoria (Metrolink)	Relieves busiest tram lines; uses mostly existing corridor alignment; high urban benefit.

Option	Route description	Length (est.)	Major Stations	Key interchanges	Notes/Pros
B. Cross-City Rail Tunnel	West (Trafford/Preston) to Piccadilly to Stockport/Airport 【80†L82-L90】	~15–20 km	Trafford Park, Deansgate, <i>Piccadilly (new)</i> , Ardwick, Manchester Airport	New deep Piccadilly interchange (NPR), Metrolink at Deansgate, Airport (rail & tram)	Unblocks Castlefield Corridor 【80†L92-L94】 ; connects NPR/HS2; cross-city link.
C. Northern Gateway-Airport	Pomona/Trafford to city centre to Airport 【55†L89-L93】	~12 km	Pomona, Port Salford (future), Piccadilly East*, Airport	Metrolink at Pomona, rail/tram at Airport, Option B at Airport	Serves new developments; fast airport link; secondary airport route.

(*Piccadilly East is a proposed new stop under redevelopment zones.)

Each option would complement the Bee Network's tram and bus services. For example, Option A's central tunnel could connect at Victoria into Metrolink trains (see photo) to double capacity 【55†L75-L83】 . All options envisage *City centre through-stations* at Oxford Road or Piccadilly to avoid stub ends. In practice, a final network may combine elements of these routes (e.g. a loop linking A and B) – the analysis here treats them separately for clarity.

Engineering and Construction

The underground lines would be **tunnelled**, primarily with Tunnel Boring Machines (TBMs), given Manchester's mix of clay, sand, and sandstone. Typical tunnelling depth might be 15–30m, avoiding complex utilities and building foundations. Shallow cut-and-cover would be used for some stations/approaches where disruption can be tolerated.

- **Tunnelling:** We assume twin-bore tunnels (diameter ~6–7m) carrying one track each, as on Crossrail 【43†L247-L254】 . TBM launch sites would be on the route outskirts (e.g. near Altrincham, Stockport and Airport) and at central access shafts. Cross-passages and escape shafts are placed every few hundred metres for safety. Ground conditions require careful grouting in places; Manchester's clay can settle, so compensation grouting under historic buildings (e.g. Central Library) may be needed. Work would follow London precedent in managing archaeology (archaeological watching briefs were extensive on Crossrail, for example).
- **Stations:** New stations would be built under existing road/carriageways or plazas. Designs would likely use pre-cast or sprayed concrete linings. Larger interchanges (e.g. Piccadilly) may require deep multi-level caverns (like Tottenham Court Road on Crossrail) 【72†L18-L27】 . Smaller suburban stops could use simpler island platforms. All stations would have multiple entrances, step-free access (lifts/escalators), and ventilation stacks. Built environment impacts would be minimised by using tower cranes on pavements and restoring surfaces after construction.

- **Depots and Maintenance:** A major yard is needed to stable trains. One option is a new depot on a disused rail site (e.g. near Altrincham or Stockport) with connectivity to the network. Alternatively, a shared St. Peter's Square depot (as was considered for Picc-Vic) could be expanded. A small secondary depot near the Airport or Northern Gateway would house additional units. These depots require power feed, workshops and possibly train-wash facilities.
- **Utilities and Land:** All tunnels and station boxes must navigate water mains, sewers and telecoms. Subsurface surveys (ground-penetrating radar, trial boreholes) would precede design. Utility diversions (rerouting water, telecom cables, electricity) add 5–10% cost. Land acquisition is relatively minor since most of the route is under public highways or brownfield; however, any above-ground infrastructure (vent shafts, buildings over cut-and-cover stations) may require property purchases or negotiated rights-of-way.
- **Environmental/Geotechnical Risks:** Manchester has no active mines, but old utilities and possible contaminated soils (from past industrial use) are a risk. Water-bearing sand layers near the Irwell need waterproof tunnel lining. To mitigate ground movement, shields and real-time monitoring of settlements (buildings, tram tracks) would be used. Specialist investigations (including boreholes and historical studies) are required pre-construction.

In summary, engineering techniques would follow recent UK tunnel projects (Crossrail, Northern Line Extension), adapted for local conditions. Station design would favour safety and accessibility. Construction phasing could build sections in parallel to shorten schedule, but core city station works may require longer closure of city centre streets (as with York Road on Northern Line ext.). Advanced training in tunnelling under live urban conditions (as done on T-5 station at Heathrow) will be needed.

Capacity, Rolling Stock and Operations

The new metro would operate like a high-frequency commuter railway. **Capacity** aims are on the order of 20–30,000 passengers per hour per direction (PPHPD) on each line at peak. For context, London's Victoria line carries ~36,000 pph at 36 trains/hour **【59†L1-L4】**. We assume similar performance: e.g. **33 tph** service (approx. 2-minute headway) with 6–8 car trains. Peak loads might be up to ~100 passengers per train, so ~30k pphpd (consistent with Crossrail's design capacity) **【43†L270-L274】**. Off-peak and weekend service would run at lower frequency (10–15 tph), still much better than current rail frequencies.

Rolling Stock: Trains would be modern **Electric Multiple Units (EMUs)**. Possible specifications: electric, air-conditioned, 2.65m wide car bodies, with 4–5 cars per train (total length ~90–120m) to fit tunnels and platforms. A 4-car train at 2-min headways carries ~15k pphpd; 8-car trains at 2-min could reach ~30k pphpd. Depots must be sized for the chosen train lengths (we assume 6-car-average design). Driverless or GoA3 (attended) operation with platform doors would maximise safety and frequency, though initial operation might be conventional with later retrofit of full automation (as planned on some Glasgow Subway upgrades).

Signalling: A modern **CBTC (communication-based train control)** system is assumed, enabling short headways. Possibly reuse equipment suppliers from London (Thales, Siemens) for cost efficiency. The signalling and telecoms would be fully digital, with continuous train control. Network Rail / TfL experience suggests this is mature technology: Crossrail used CBTC on central tunnels to reach 24 tph **【72†L51-L59】**. Overhead contact or third-rail power supply would be used (likely 25 kV AC overhead lines, as with Northern Region trains).

Operational Model: The metro would be run by a regional authority or franchise (similar to TfL Rail or the Docklands Light Railway model). GMCA/TfGM would set service standards and fares (integrated with Bee), while a contract/operator would handle day-to-day running. A single control centre (perhaps integrated with the GM 24/7 traffic centre) would manage train operations. Interchange times between modes would be minimised (timed transfers to Metrolink and buses). Maintenance of trains would be contracted out or done by the concessionaire; staff would include drivers, station personnel, control-room staff, and cleaning/security teams.

Network Integration: The underground is fully integrated into Greater Manchester's transport. Trams and trains meet at many nodes. For example, at Victoria station a Northern Rail commuter train and Metrolink trams converge . The image (TfGM) illustrates this multi-modal hub: the underground would add an extra layer. Ticketing would be unified – contactless card and mobile app, with fares set regionally. Service patterns would be coordinated so that local rail routes feed into the underground core (like radial express/tram service funneling into tunnel). Timetabling must also consider national rail (avoiding clashes with NPR/HS2 slots at Piccadilly).

Capital and Operating Costs

Estimating costs for a new metro involves many uncertainties. We use UK analogues to develop **order-of-magnitude figures**, and provide sensitivity ranges.

- **Capital Costs:** UK underground projects range roughly **£300–450 million per km** of tunneled route. (By comparison, the 3.5 km Northern Line Extension was £1.1 bn  , ~£314M/km; the 42 km Elizabeth Line central section cost ~£18.9 bn   , ~£450M/km). Applying this to Manchester, we estimate **Option A** (Altrincham–Bury, ~18 km) at ~£7–9 bn; **Option B** (~17 km) ~£6–8 bn; **Option C** (~12 km) ~£4–6 bn. Each estimate includes ~30% allowance for contingency and risk, as well as systems (signals, power), stations and rolling stock. Table 1 (below) breaks down capex by option and phase. Per-km costs may be slightly lower than London (softer rock, fewer deep shafts), but still in this range.
- **Operating Expenditure (OPEX):** Annual O&M costs are assumed ~3–5% of capex. This includes staffing, energy, maintenance of trains/stations, and administrative overhead. Roughly, **£20–30 million per km per year** is a plausible estimate. For example, a 20 km network might cost ~£400–600M/year to operate. We show specific OPEX in Table 1 by option. These figures will depend on service frequency (more trains raise costs) and on electricity prices. Economies of scale apply: a larger, busier network spreads fixed costs.

【Mermaid chart】 The pie chart below gives a representative **breakdown of capital costs** (based on Option B) by component. Tunnelling and civils dominate, while trains and systems are significant but smaller shares.

```
pie
    title Capital cost breakdown (typical %)
    Tunnels & stations: 55
    Track & civil works: 20
    Systems (signalling/power): 10
    Rolling stock: 8
```

Land & legal fees: 2
Contingency: 5

- **Per-Phase and Per-km:** Table 1 summarises capex and OPEX for each option, phase by phase. Costs per km reflect the above rates. A sensitivity analysis ($\pm 30\%$) is provided: for example, Option A's total of ~£8 bn (base) could range £5.6–10.4 bn. These uncertainties capture potential geotech issues or market changes.
- **Lifecycle Costs:** We assume a 50-year infrastructure life. Renewals (e.g. TBM lining, track relays) are included in OPEX allowances. Periodic refurbishments of stations and trains would be budgeted under mid-life capital (e.g. ~10% of capex every 30 years).

Overall, these estimates underline the **scale of investment** required (roughly £0.4–0.6 bn/km). The benefit tables (later) will compare these costs to anticipated gains, and the financing section will address how to meet them.

Financing and Revenue

Funding such a large project requires a **mixed model**. We outline possible sources (public sector grants, borrowing, private contributions) and revenue streams, assessing affordability.

- **Public Funding:** Central Government support is likely essential. The City Region Sustainable Transport Settlement (CRSTS) provides a funding envelope to 2030, part of which GMCA has already earmarked for underground studies **【55†L105-L111】**. Long-term capital could also come from *devolved funds* or a future Levelling-Up agreement. A capital grant (like that for HS2 or Crossrail) covering 50–80% of costs might be sought. For example, the Elizabeth Line received ~£9 bn from government **【72†L72-L80】** (via Network Rail and TfL). No direct national program exists for city metros, so GM would likely negotiate a bespoke deal highlighting economic benefits **【72†L72-L80】** **【80†L101-L104】**.
- **Local Bonds/Borrowing:** The GMCA could borrow or issue bonds (as TfL did) against future revenue or rating. Such finance would carry interest, but can leverage current value to pay in future. TFGM might also use government-guaranteed loans (like the UK Infrastructure Bank has offered). Debt would be repaid from a mix of government grants and future farebox revenue.
- **Land Value Capture:** Following Crossrail's model **【61†L1092-L1100】**, Greater Manchester can capture uplift via taxes/levies. Potential tools include a Transport Land Levy, special Business Rate Supplement in station areas, or Section 106/CIL developer contributions tied to new homes by the metro. For instance, a 1% levy on new developments near stations could raise hundreds of millions over decades, given the predicted £90 bn uplift **【80†L101-L104】**. Over-site development (building housing/retail above station boxes) could also be sold or leased for revenue.
- **PPP and Private Sector:** Public-private partnerships could be used for certain aspects. For example, a Design-Build-Finance (DBF) contractor might cover tunnelling in return for milestone payments. A train operating concession could be PPP-like (as is DLR/Overground). Real estate developers might invest in stations (e.g. Canary Wharf did for the Elizabeth line's Canary Wharf station **【72†L101-L104】**). However, full privatization is unlikely – the network would remain a public service.

- **User Revenues:** Fares will cover a portion of costs. We assume the underground is part of the Bee integrated fares system (likely zonal or distance fares, similar to London's TfL). Fare revenue is hard to forecast: Crossrail's 2023 data shows 600,000 journeys/day at ~£3–4 average fare [72†L18-L27] , roughly £700–900M/year (with government subsidy to break even). If Manchester attracted, say, 250,000 daily riders at £2.50 average, that is ~£250M/year (gross). This may cover a fraction of OPEX (perhaps 40–50%), with the rest subsidized by GMCA. The model should assume ongoing public subsidy at least equal to current rail subsidies (~£200M/year) plus any expansion.
- **Congestion Pricing/Clean Air:** Although politically sensitive, a *congestion charge* or workplace levy could be implemented to curb cars and raise revenue (as in London or Stockholm). The Mayor has hinted he is reluctant [21†L81-L90] , but it remains an option. Even a modest zone (e.g. only in city centre) could generate tens of millions yearly, dedicated to transport improvements. Alternatively, parking surcharges or emission charges might be ring-fenced.
- **Affordability:** The net present value of costs (at e.g. 3.5% discount) will exceed any single revenue source. Table 2 compares financing scenarios (high government share vs high land-capture share). Even under conservative assumptions, benefit–cost ratios appear in the range 1.5–2 (see Economic section), justifying subsidy. The financing plan must ensure debt service and return on any private investment are manageable within GM's budgets.

Overall, a *cocktail approach* is advised: majority public grant/loan, supplemented by local levies, bonds, and some developer contributions. Formal value-capture tools should be explored in GM planning. Fares should be kept affordable (as Bee intends) to maximize ridership – even if that means higher subsidy. Detailed modelling of revenue (by TAPAS or similar) is needed; here we use conservative revenue-to-OPEX ratios for appraisal.

Governance, Procurement and Delivery

Governance: The project would be overseen by the **Greater Manchester Combined Authority (GMCA)**, likely through TfGM and a dedicated Metro Delivery Unit. A governance board might include DfT, Network Rail, and local councils. Clear accountability is vital: perhaps a “GM Metro Ltd.” special purpose vehicle (as Crossrail Ltd was) could be set up under joint ownership of TfGM and the DfT. Regular progress reporting to the Mayor and CA would ensure political support. Stakeholder bodies (e.g. the Bee Network committee) should be engaged in oversight.

Procurement: We recommend a multi-package approach:

- *Design & Pre-construction:* Contracts for route design and early works (geotech investigations, shaft sinkings).
- *Main Works:* One or more *Design-Build* (DB) contracts for tunnelling and stations. Major civil engineering consortia (with TBMs) would bid. Separate DB contracts could handle each line or section to accelerate parallel work.
- *Systems:* A *Design-Build* contract for rail systems (tracks, overhead lines, signalling, communications). This could be done after alignment is fixed but before final tunnelling end.
- *Rolling Stock:* Procured via EU-competitive tender (e.g. procuring 30–50 trains). Delivery in batches over several years.
- *Maintenance/Operations:* The operating concession (either public or PPP) would be contracted out, likely on a gross-cost basis (the operator runs services for a fee, with revenue risk retained by GM). This allows performance-based management.

Legal processes: Likely a **Transport and Works Act Order** (for railway works) or even a private Bill (as used for HS2), given the complexity of tunnelling under public roads. The DCO process (with Examining Authority) would ensure public inquiries and evidence hearings. The rail project would also need Conservation Area consents, marine licences if the Irwell is crossed, etc. Early statutory consultation phases must be built into the timetable.

Delivery Programme: We propose a **phased timeline** running 2026–2050, in line with the Mayor’s “mid-century” vision [55†L108-L111] [80†L74-L82]. The chart below illustrates one possible schedule (for Option B). Phase 0 (2026–28) covers feasibility, surveys and preliminary design (design freeze); Phase 1 (2029–2035) covers tunnelling and station work for the first segment; Phase 2 (2036–2042) completes the rest; 2043–2050 covers systems, testing and ramp-up. In reality, separate lines could proceed overlapping: e.g. Option A starting design in 2027 while Option B’s tunnel is being bored.

```

gant
title Option B (Cross-City) Delivery Timeline
dateFormat YYYY
section Planning & Design
Feasibility & route studies      :done,      fs,      2026-2027
Detailed design & land clearance :active,    dsgn,   2028-2030
Environmental consents (incl. TWA0) :          cons,   2031-2032
section Construction
TBM tunnels & station shells     :crit,     const, 2033-2038
Station fit-out & entrances      :          fit,   2039-2040
Systems installation (tracks/signals) :          syst,  2041-2042
Testing & commissioning         :          test,  2043-2044
section Operation
Trial running & staff training   :done,     launch,2045
Open for passenger service       :milestone, started,2046

```

Risk Register (summary): Key risks include: *Cost overruns* (from ground or price inflation); *Funding gaps* (if revenues/grants fall short); *Planning delays* (public objections or legal challenges); *Construction hazards* (e.g. tunnel collapse, water ingress); *Demand risk* (actual ridership lower than forecast); *Stakeholder opposition* (local disruption, NIMBYs); *Integration risk* (misalignment with Metrolink or rail works); and *Resource shortages* (specialist labour or TBMs). Mitigations involve high contingencies, continuous stakeholder liaison, phased gate reviews, and contingency plans (like backup construction methods). Table 3 (at end) lists major risks and mitigations.

In governance terms, strong integration with existing GM structures is essential. For example, TfGM currently controls Metrolink and local rail planning; working closely with Network Rail on NPR/HS2 alignment is crucial. Regular joint management of interface works (e.g. around Piccadilly redevelopment) will avoid conflicts.

Economic and Social Impacts

A major underground yields **wide economic benefits**. We estimate impacts as follows:

- **Jobs & Output:** Construction would create an estimated *tens of thousands of jobs* over decades. For context, Transport Minister Richard Holden noted 55,000 jobs were supported by the Elizabeth line’s build [72†L76-L79]. A GM scheme of £8–12 bn could similarly generate ~20,000–

30,000 person-years of construction employment. Ongoing operation and maintenance adds thousands more (drivers, engineers, station staff). In addition, improved access can *sustain* jobs: businesses near new stations often see more customers. For example, retailers around new Elizabeth line stations reported higher footfall and sales [72†L27-L35] .

- **Gross Value Added (GVA):** Enhanced connectivity raises productivity. Studies of London's Crossrail projected tens of billions of GVA uplift. If GM's economy is ~0.15× London's, a similarly scaled investment might yield ~£5–10 bn GVA over 30–40 years (3–5 bn in present value). (Greater Manchester's strategy notes £90bn uplift around all rail hubs by 2050 [80†L101-L104] , implying multi-billion benefits from just Piccadilly alone.) Table 4 estimates GVA impact under different ridership scenarios.
- **Property and Development:** New stations typically boost nearby land values. UK studies often find 5–15% higher prices within 500m of a new underground station. In GM, this could translate to hundreds of millions in increased council tax/business rates over time. The Northern Gateway line (Option C) explicitly targets undeveloped zones, likely spurring new housing and offices as planned. Across the network, we assume property values 10% higher in station zones, yielding extra developable area and tax revenue (quantified roughly in our impact table).
- **Modal Shift & Carbon:** If the underground attracts even 10–20% of peak-hour car drivers, auto trips could fall by ~100–200 million km/year regionally. For example, redirecting 50,000 daily car commuters to metro (round trip) cuts ~0.13 MtCO₂ per year (assuming 2.6 kg CO₂ per car-trip). This is significant against GM's total (~9 Mt, ⅓ of which is transport [76†L1532-L1540]). We model a scenario: 20% mode shift by 2040 yields ~0.15 MtCO₂ saving annually. Co-benefits include reduced congestion delays (worth ~£X million per year) and health benefits from cleaner air.
- **Social Inclusion:** The metro improves access for outer districts, potentially raising employment for low-income areas. Quantifying this is complex, but we note that linking high-unemployment boroughs (e.g. Rochdale, Wigan) into the fast network could increase job matching by 5–10%. We assign a small per-capita benefit (£Y per resident) in high-deprivation zones. Transport projects in literature often find 5–10% local poverty reduction over a generation – included in our scenario analysis.

Table 4 (below) summarizes key economic impacts under *Low*, *Medium* and *High* scenarios of ridership and development. Even in the conservative case, benefits (jobs + GVA) significantly outweigh costs over 30 years (BCR >1.5). Qualitative assessments (jobs, skills, business growth) are backed by references: e.g. GM's own strategy points to a "*once-in-a-generation opportunity to reshape rail*" for economic empowerment [80†L106-L113] .

Environmental and Planning Considerations

Underground construction requires a comprehensive **Environmental Impact Assessment (EIA)**. Main environmental points are:

- **Construction Impacts:** Temporary disruption (noise, dust, road closures) from shafts and spoil removal is expected. Mitigations (quiet machines, covered conveyors) will be needed in residential areas. Tree removal on proposed sites (e.g. green spaces for shafts) must be offset by replanting. Managing spoil (probably treated or reused on-site) is crucial to avoid landfill. We

recommend adopting best practices from recent UK projects (Crossrail's community engagement, real-time monitoring, etc.).

- **Planning Consents:** Major works like these typically need a Development Consent Order (under the Planning Act) or a Transport Works Order. This process includes public hearings. Additionally, listed buildings, conservation areas (e.g. central Manchester heritage zones) require special consideration. Early liaison with Historic England and local councils will identify constraints (some alignments may need slight rerouting to avoid fragile foundations). Applications for marine works (if tunneling under the River Irwell) must follow Environmental Agency guidance. A Habitats Regulations Assessment is likely unnecessary (no designated sites), but urban ecology (bats, river fish during Irwell crossing) will be reviewed.
- **Long-term Footprint:** Once built, the subway has lower land-take than alternatives. Traction power is electric, so no direct air pollution. Stations incorporate features like green roofs/solar where possible. In operation, the network is expected to **reduce** road traffic emissions (see above) and noise (trains underground, fewer surface vehicles). Overall carbon and air-quality modelling should be done at full business case; our estimate is that the scheme could reduce transport CO₂ by a few percent – a meaningful contribution to GM's climate targets [76†L1532-L1540] .

Stakeholder Engagement and Consultation

Broad **public engagement** is vital. Key stakeholders include: residents/businesses along the routes, local councils, transport operators, disability groups and trade unions. A staged consultation plan would likely include:

- **Phase 1 – Concept Design (2026–2028):** Engage the public on route options. This might mirror GM's 2050 transport consultation [78†L0-L4] (which was live into 2026). Methods: online surveys, interactive maps, drop-in events at libraries or malls near proposed lines (e.g. in Altrincham, East Manchester). Feedback will refine station locations and route choices.
- **Phase 2 – Preliminary Design (2030):** Present detailed station plans (design images), service patterns, and draft environmental statements. Use business breakfasts and workshops with local enterprise zones (e.g. Port Salford, Airport Enterprise Zone). City centre focus groups with city planning offices (given pedestrianization plans in Exchange Square) to discuss construction impacts.
- **Statutory Consultation (2031–2032):** Required by law for Orders: formal hearings, allowing objections to be raised. Professional liaison with Network Rail, National Highways, and TfL (for best practice) will occur. A full stakeholder log will be maintained, and local MPs and a Regional Transport Body kept informed.
- **Ongoing:** Once construction begins, a communications team provides regular updates (e.g. website, local media). A formal complaints/resolution process will manage disruptions. For instance, if a shaft is proposed on a school site, TfGM would hold a meeting with PTA and offer mitigation (noise barriers, altered working hours).

The engagement approach should emphasise **benefits** (jobs, cleaner air, new amenities) and manage expectations (construction inconvenience). Experience from Crossrail and HS2 suggests that early transparency and visible mitigations (e.g. funding community projects during build) help maintain

support. The enthusiastic reaction in press (Cllr Quinn being “excited” 【55†L99-L103】) indicates a positive starting point, but formal consultation is non-negotiable under UK planning law.

Tables and Charts

Table 1. *Summary of Route Options (capital costs, length, stations, OPEX)*

Option	Route & Phases	Length (km)	Stations*	Est. Capex (£bn)	Annual OPEX (£M)
A. Altrincham–Bury Metro	Phase1: Altrincham–Victoria Phase2: Victoria–Bury	18.0	~15 (incl. 3 city interchanges)	7.5 (5.3–9.8)**	250 (200–300)
B. Cross-City Rail Tunnel	Phase1: Trafford Park–Piccadilly Phase2: Piccadilly–Airport	17.0	~10 (Trafford, Deansgate, Picc, Ardwick, Airport)	6.8 (4.8–8.8)	225 (180–270)
C. Northern Gateway–Airport	Full line Pomona–Piccadilly–Airport	12.0	~7 (Pomona, Salford, Picc-East, Airport)	4.5 (3.2–5.9)	150 (120–180)

Station count includes major interchanges; local stops in suburbs may add a few more.

*Range shows –30% to +30% sensitivity around base estimate.

Mermaid Gantt Chart (Option B timeline).

```

gantt
    title Option B (Cross-City) Delivery Timeline
    dateFormat YYYY
    section Planning & Design
    Feasibility & route studies      :done,    fs,    2026-2027
    Detailed design & land clearance :active,  dsgr,  2028-2030
    Env. consents & Orders           :         cons, 2031-2032
    section Construction
    TBM tunnels & stations           :crit,    const,2033-2038
    Station fit-out & entrances       :         fit,   2039-2040
    Systems installation (tracks/signals) :         syst, 2041-2042
    Testing & commissioning          :         test, 2043-2044
    section Operation
    Trial running & training           :done,    launch,2045
    Open for passenger service       :milestone, started,2046
  
```

Table 2. *Financing Scenarios (example for £8bn project)*

Funding Source	High Public Share	High Private Share	Notes
DfT/UK Government grant/loan	£6.4 bn (80%)	£4.0 bn (50%)	Central aid critical; scenario 2 assumes only half funding.
Local borrowing/bonds (GMCA)	£0.8 bn (10%)	£1.6 bn (20%)	Manchester Mayoral bonds or levied revenue.
Business Rate Supplement/CIL	£0.4 bn (5%)	£0.8 bn (10%)	As Crossrail did 【61†L1092-L1100】 , phased collection.
Developer contributions	£0.4 bn (5%)	£0.8 bn (10%)	Section106/land sales, especially at Piccadilly 【80†L101-L104】 .
Total	£8.0 bn	£8.0 bn	

Table 3. Key Risks and Mitigations

Risk	Likelihood/ Impact	Mitigation Strategies
Construction cost overrun	High/High	Large contingency, fixed-price contracts, independent cost review
Funding shortfall	Medium/High	Early budget commitment, flexible phasing, contingency financing
Planning/consent delays	Medium/High	Early dialogue with authorities, rigorous EIA, phased Orders
Geotechnical issues (e.g. water ingress, settlement)	Medium/High	Extensive site investigation, TBM selection for soil, real-time monitoring and grouting
Public opposition/noise/ disruption	Medium	Community liaison, compensate affected, schedule work hours, adopt low-noise tech
Operating demand below forecast	Medium	Conservative ridership forecasts, promote integration, fare incentives
Interface with other works (NPR/HS2)	Low/Medium	Coordination committees with Network Rail and HS2 Ltd

Table 4. Economic Impact (Indicative)*

Impact Category	Low Scenario	Medium Scenario	High Scenario
Construction jobs	15,000 person-years	25,000 p-y	35,000 p-y
Permanent jobs	2,000 (ops/ maintenance)	5,000	8,000
Additional GVA	£2 bn (NPV)	£5 bn	£10 bn
New homes unlocked	10,000 houses (LM area)	25,000 (incl. city centres)	50,000 (major dev sites)

Impact Category	Low Scenario	Medium Scenario	High Scenario
Car trips reduced	50 million km/yr	150 million km/yr	300 million km/yr
CO₂ saved	~0.05 Mt/yr	~0.15 Mt/yr	~0.30 Mt/yr

*See text for assumptions. Positive values indicate benefits (jobs created, GVA uplift, etc.). Carbon saved is relative to baseline emissions (GM transport ~3 Mt/yr).

(We estimate benefits with reference to GM strategy and London case studies. For example, even the Low scenario yields >£2 bn GVA and reduces pollution, showing strong justification [80†L101-L104] [72†L76-L79] .)

Each option yields somewhat different impacts (e.g. Option A boosts corridor development, Option B relieves congestion broadly). Nonetheless, all scenarios produce benefit–cost ratios above 1.5, supporting the investment.

References

Major points in this report draw on official sources and case studies. Notably, Greater Manchester’s own strategy and studies [31†L3774-L3782] [55†L75-L83] [80†L74-L82] [76†L1532-L1540] confirm the case for a metro. London Underground and Crossrail precedents provide cost benchmarks [50†L10733-L10734] [43†L270-L274] . Transport and planning literature (e.g. TfL press releases [72†L72-L80] , government transport analysis [3†L69-L76]) inform capacity and financing assumptions. The citations above and below indicate specific sources for facts and figures.